BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

BYATARAYANAPURA DIVISION

BYATARAYANAPURA SUB DIVISOIN

Name of the Work : **Construction of Temprovary Immerssion Tank for Ganesha Idols in ward no. 09, Amruthahalli Byatarayanapura Sub Division,**

Estimated Cost : 10.00 Lakhs

ಅಂದಾಜು ಪಟ್ಟಿಯ ವರದಿ

ವಿಷಯ: ವಾರ್ಡ್ ನಂ. 09(ಅಮೃತಹಳ್ಳಿ) ವ್ಯಾಪ್ತಿಯ Construction of Temprovary Immerssion Tank for Ganesha Idols in ward no. 08, Amruthahalli Byatarayanapura Sub Division, ಕಾಮಗಾರಿಗೆ ಅನುಮೋದನೆ ನೀಡುವ ಕುರಿತು.

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ವಾರ್ಡ್ ನಂ. 09(ಅಮೃತಹಳ್ಳಿ) ವ್ಯಾಪ್ತಿಯ Construction of Temprovary Immerssion Tank for Ganesha Idols in ward no. 08, Amruthahalli Byatarayanapura Sub Division,ಕಾಮಗಾರಿಗೆ ರೂ. 10.00 ಲಕ್ಷಗಳ ಅಂದಾಜು ಮೊತ್ತದಲ್ಲಿ 2022-23 ನೇ ಸಾಲಿನ ಆಯವ್ಯಯದ ಲೆಕ್ಕಶಿರ್ಷಿಕೆ ಪಿ-3726ರ ಕಾಮಗಾರಿ ಕ್ರಿಯ ಯೋಜನಾ ಪಟ್ಟಿಯಲ್ಲಿ ಕಾಮಗಾರಿಯನ್ನು ನಿರ್ವಹಿಸಲು ಅವಕಾಶ ಕಲ್ಪಿಸಲಾಗಿರುತ್ತದೆ.

ಅದರಂತೆ ವಾರ್ಡ್ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ ಗಣೇಶ ಮೂರ್ತಿಗಳನ್ನು ವಿಸರ್ಜನೆ ಮಾಡಲು ಅನುಕೂಲವಾಗುವಂತೆ ತಾತ್ಕಾಲಿಕವಾಗಿ ಕಲ್ಯಾಣಿಗಳಲ್ಲಿ ವ್ಯವಸ್ಥೆ ಕಲ್ಪಿಸಲು ಸ್ಥಳ ಪರಿಶೀಲನೆ ಮಾಡಿ, ಅಗತ್ಯ ಅಂಶಗಳನ್ನು ಅಳವಡಿಸಿಕೊಂಡು ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ಈ ಕೆಳಕಂಡ ಐಟಂಗಳನ್ನು ಅಳವಡಿಸಿ ತಯಾರಿಸಲಾಗಿರುತ್ತದೆ.

1. ಹಾಲಿ ಇರುವ ಕಾಲ್ಯಾಣಿಯಲ್ಲಿ ತುಂಬಿರುವ ಹೂಳನ್ನು ತೆಗೆದು ಹೊರಸಾಗಿಸುವುದು.
2. ಗುಂಡಿಯ ಸುತ್ತಲು ಬ್ಯಾರಿಕೇಡಿಂಗ್ ಮಾಡುವುದು
3. ಶ್ಯಾಮಿಯಾನ, ಬೆಂಚು, ಚೇರ್, ಲೈಟಿಂಗ್ಸ್ ವ್ಯವಸ್ಥೆಯನ್ನು ಒದಗಿಸುವುದು
4. ವಿಸರ್ಜನಾ ಗುಂಡಿಗೆ ಸ್ವಚ್ಚವಾದ ನೀರನ್ನು ತುಂಬಿಸುವುದು.
5. ಜನರೇಟರ್, ಡಿ-ವಾಟರಿಂಗ್ ಮೋಟರ್ ಅನ್ನು ಒದಗಿಸುವುದು.
6. ಟ್ರಾಕ್ಟರ್ ವಾಹನ ಹಾಗೂ ಕೂಲಿ ಆಳುಗಳನ್ನು ಒದಗಿಸುವುದು.
7. ಸದರಿ ಕಲ್ಯಾಣಿಯಲ್ಲಿ ಗಣೇಶ ವಿಸರ್ಜನೆ ನಂತರ ತುಂಬಿರುವ ಹೂಳ ಮತ್ತು ಇತ್ಯಾದಿ ಗಣೇಶ ಮೂರ್ತಿ ಅವಶೇಷಗಳನ್ನು ಹೊರಸಾಗೊಸಿವಿದಿ. ಇತ್ಯಾದಿ ಅವಶ್ಯಕ ಅಂಶಗಳನ್ನು ಅಳವಡಿಸಿಕೊಂಡು ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ತಯಾರಿಸಲಾಗಿದೆ.

ಮೇಲ್ಕಂಡ ಅಂಶಗಳನ್ನು ಅಳವಡಿಸಿ ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ಬೆಂಗಳೂರು ವೃತ್ತ, ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ, 2018-19, 2021-22 ರ ದರ ಪಟ್ಟಿ ದರಗಳನ್ನು ಹಾಗೂ ಕೆಲವು ಅನುಮೋದಿತ ದರಗಳನ್ನು ಅಳವಡಿಸಿ ತಯಾರಿಸಲಾಗಿರುತ್ತದೆ. ಸದರಿ ಅಂದಾಜು ಪಟ್ಟಿಗೆ 2022-23ನೇ ಸಾಲಿನ ಅನುದಾನದ ಲೆಕ್ಕ ಶಿರ್ಷಿಕೆ ಪಿ-3726ರ ಅಡಿಯಲ್ಲಿ ಅನುಮೋದಿಸಿ, ಆಡಳಿತಾತ್ಮಕ ಅನುಮೋದನೆ, ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿ ಕಾಮಗಾರಿಯನ್ನು ತುರ್ತಾಗಿ ಕೈಗೊಳ್ಳಬೇಕಾಗಿರುವುದರಿಂದ ಟೆಂಡರ್ ಕರೆದು ಗುತ್ತಿಗೆದಾರರನ್ನು ನೇಮಿಸಿ ಕಾರ್ಯದೇಶ ನೀಡಲು ಈ ಮೂಲಕ ತಮ್ಮಲಿ ಕೋರಲಾಗಿದೆ.

ಸಹಾಯಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ಉಪ ವಿಭಾಗ
ಬಿ.ಬಿ.ಎಂ.ಪಿ., ಬೆಂಗಳೂರು-26

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of work: Construction of Temprovary Immerssion Tank for Ganesha Idols in ward no. 09, Amruthahalli Byatarayanapura Sub Division,

								Estimate Cost Rs.	1000000.00
Sl No	**Description of item**	**Unit**	**No**	**L**	**B**	**D**	**Qty**	Rate	**Amount**
1	Providing Causal Labours (Unskilled mazdoor Heavy) (PWD SR 2021-22 Page No. A-52 / Sl No. IV 1)	Per Day							
	During day = 10 labours		1	10	11		**110.00**		
	During Night = 20 labours		1	15	11		**165.00**		
	Labour for Tractor		3	3	11		**99.00**		
							374.00	486.22	**181846.00**
2	Hire Charges for Shamiyana Side wall Size 10X8 ft (Election Rates Sl No. 22E)	Per Wall							
			1X12x11				**132.0**	350.00	**46200.00**
3	Hire Charges of Cloth and Pipe Shamiyana (Election Rates Sl No. 22C)	Sft							
			1X11	1000.0			**11000.0**	14.00	**154000.00**
4	Hire Charges for Armless Plastic Charis (Election Rates Sl No. 27)	No							
			1X 50x11				**550.0**	5.50	**3025.00**
5	Hire Charges for Wooden Table of size 6ft x 2ft	No							
	Rs. 40 Per Day		10x11				**110.0**	40.00	**4400.00**
6	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 III b)	Mtrs							
			100x11				**1100.00**	11.00	**12100.00**
	Rs. 11 Per /Day								
7	Generator 100 KVA (PWD SR 2021-22 (P. A-44 / Sl No. 33)	Hrs							
			6	8			**48.0**	1303.00	**62544.00**
8	Hire Charges of Focus White Light (Election Rates Sl No. 40E)	Per Light/Day							
			5	11			**55.00**	650.00	**35750.00**
9	Hire Charges of Halogen Bulb (Election Rates Sl No. 40A)	Per Light/Day							
			10	11			**110.00**	260.00	**28600.00**
10	Hire Charges of Serial Light (Election Rates Sl No. 40f)	Per set/Day							
			55	11			**605.00**	40.00	**24200.00**
11	Hire Charges of Thrible Line Barrcade (Election Rates Sl No. 48B)	Per/Mtrs							
			1X11	100.0			**1100.0**	80.00	**88000.00**
12	HOM for pumping of 3.5 KL / Hr capacity pump (Page No. L, Sl. No. 49) 2018-19 SR	Hr							
	Pumping of Waste Water from Immersion Tank		1X5X11dayX6 hr/day				**330.00**	42.00	**13860.00**
13	Supply of water Through water Tank for filling Tank	Per load							
			1X11X15				**165.00**	360.00	**59400.00**
14	Hire charges for 50 HP tractor including fuel, transportation, all leads and lifts etc., complete as directed (I.No 20, Code 1024, P.No XLVIII) PWD SR 2018-19)	Day							
			2	11			22.00		
							22.00	2129.00	**46838.00**

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
15	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil in ving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum							
	For Destlting before and After		2	15.00	13.00	1.60	624.00		
							624.00	137.80	**85987.00**
	Basic Rate	130.00							
	Area Weightage @ 6%	7.80							
	Total	**137.80**							
									846750.00
16	Add Applicable GST (18%)								**152415.00**
17	Miscesallaneous Charges	L/S							**835.00**
									1000000.00

CERTIFICATE:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per PWD SR 2018-19, 2021-22 and pproved Rates Approved by District Election officer, Bangalore
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Assistant Engineer

Executive Engineer
Byatarayanapura Division

Assistant Executive Engineer
Byatarayanapura Sub Division

ADMINISTRATIVE APPROVAL
Accorded For Rs. 10.00 Lakhs only
Head of A/c. P3726
Div. Ref No. 09 Date 18/8/22
AE EE(BTP)

TECHNICAL SANCTION
Accorded For Rs. 10.00 Lakhs only
Head of A/c. P3726
Div. Ref. No. 09 Date 18/8/22
AE EE(BTP)